


No. Pages : 14

TOP SECRET

COPY NO.: 55

Joint Photographic Intelligence Report

**LAUNCH COMPLEX "E"
SURFACE-TO-SURFACE MISSILE FACILITIES
KAPUSTIN YAR/VLADIMIROVKA
MISSILE TEST CENTER, USSR**



ARMY




NAVY



CIA


VITAL RECORDS COPY

PIC/JR-21/60
OCTOBER 1960



25X1

Published and Disseminated by
CENTRAL INTELLIGENCE AGENCY
PHOTOGRAPHIC INTELLIGENCE CENTER

This document contains information usable only within the  **5X1**
It is to be seen on a MUST-KNOW BASIS ONLY BY PERSONNEL ESPECIALLY INDOCTRINATED AND AUTHORIZED. Reproduction is prohibited unless approved by the originator.

Declass Review by NIMA / DoD

TOP SECRET

WARNING

This material contains information affecting the National Defense of the United States within the meaning of the espionage laws, Title 18, USC, Secs. 793 and 794, the transmission or revelation of which in any manner to an unauthorized person is prohibited by law.

LAUNCH COMPLEX "E"
SURFACE-TO-SURFACE MISSILE FACILITIES

KAPUSTIN YAR/VLADIMIROVKA
MISSILE TEST CENTER, USSR

PIC/JR-21/60

OCTOBER 1960

PIC/JR-21/60

PREFACE

This joint photographic intelligence report has been prepared by the Army, Navy, and Central Intelligence Agency as a partial answer to Army SRI-59T-1-59 and SRI-61T-1-59, Navy DNI Project 436-59 and 417-60, Central Intelligence Agency RP/E/R84/59 and SI/R56/59, and JPRC/R22/59. This report is the first of several presenting a detailed photo analysis on the Complexes that form the Surface-to-Surface Missile Facilities at the Kapustin Yar/Vladimirovka Missile Test Center.

Whenever applicable the reports will present a comparative analysis of the [redacted] photography, and the line drawings will portray in green all changes and additions subsequent to the [redacted] coverage. Letter designations have replaced initially assigned zone numbers, but the latter are referenced parenthetically throughout this and the future reports. All reported azimuths are referenced from true north, and the term miles refers to nautical miles.

25X1

25X1




FIGURE 1. KAPUSTIN YAR/VLADIMIROVKA MISSILE TEST CENTER. This map shows the areas of the Surface-to-Surface Missile Facilities, and, specifically, Launch Complex "E". Significant additions since [] throughout the Test Center are shown in green.

TOP SECRET

TOP SECRET

PIC/JR-21/60

~~TOP SECRET~~

25X

PIC/JR-21/60

INTRODUCTION

The Surface-to-Surface Missile Facilities, which are located primarily in the central part of the Kapustin Yar/Vladimirovka Missile Test Center and constitute its largest group of facilities, comprise the following eight complexes: Launch Complexes "A", "B", "C" and "E"; Troop Training Launch Complexes "F" and "G"; the Rocket Launch Complex, and the Test and Support Complex (Figure 1). The former V-2 Launch Site, now abandoned, is also located in the area of the SSM Facilities. All these complexes are supported from Kapustin Yar with the exception of Troop Training Launch Complex "G" which receives support from Vladimirovka.

Launch Complex "E", under construction in [] is the most recent of the SSM launch complexes. Its presence is indicative of a new missile system under development. The area of Complex "E" was covered by aerial photography on [] and again on [] [] At the time of the [] coverage the Complex was in a late stage of construction; there was no evidence on the [] photography suggesting its eventual establishment. It is estimated that the Complex should have become operational by mid 1960.

25X1

25X1

25X1

25X1

25X1

Launch Complex "E" is road served and consists of a double-fenced launch area (Launch Area "E") and a single-fenced Assembly and Checkout Area (Figure 2). Launch Area "E" is situated at 48-46N 46-18E, 28 miles by road from Kapustin Yar. The Assembly and Checkout Area is located four miles to the south of the launch area, adjacent to the support area of Launch Complex "A" (Zone 7).

No guidance or instrumentation facilities have been identified as being associated with Complex "E", and, therefore, the general direction of fire cannot be determined. However, it should be noted that the orientation of the large square launch pad (Item 1, Figure 4) is about 50° from north or nearly coincident with that of the rhombic antennas under construction near Launch Complex "C" (See CIA/PIC/JB-11/60). If firings are to be in an easterly direction, as evidenced at other SSM launch complexes, then

~~TOP SECRET~~

25X1

PIC/JR-21/60




FIGURE 2. LAUNCH COMPLEX "E". This illustration shows the location and association of areas comprising this Complex.

these firings would be over a diagonal of the pad. At the time of the [redacted] photo coverage, no water, power, or communications lines appeared to connect the assembly and checkout area with the launch area.

25X1

Two inactive areas of minor importance, an Early Construction Area and an Unidentified Area, are located to the west of and along the road to the launch area. The Early Construction Area, delineated by a firebreak, covers about 20 acres. It contains seven single-story buildings of various sizes and a group of 38 tent bases. The area appears abandoned and apparently was active only during the early construction phase of the launch area. The Unidentified Area, also delineated by a firebreak and covering about 35 acres, was probably in existence prior to the construction of the road to the launch area, since the road is superimposed over the extreme western end of the surrounding firebreak. There are no structures or buildings in the area, and there is no evidence that it will be used in the future.

PIC/JR-21/60

LAUNCH AREA "E"

Launch Area "E" (Figures 3 and 4), situated at the terminus of a new all-weather road from Launch Complex "A", is a nearly square double-fenced area 1,840 by 1,680 feet covering about 70 acres. Security consists of two perimeter fences, 160 feet apart, with guard towers at each corner, and a security building. Between the fences is a ditch with short offshoots to each guard tower. Significant items in the launch area include a launch pad, a control bunker, a vehicle revetment, a vehicle bunker, and two semiburied tanks. A concrete service road 25 feet wide enters the area from the west, tees near the control bunker, and provides access to the large square launch pad. Other items within the area include three circular ground scars and eight single-story general support and maintenance buildings. Sufficient room is available in the northern half of the launch area for the construction of another large launch pad. However, at the time of photography there was no evidence that a second pad was being constructed. The location and orientation of the predicted pad is shown in form lines on Figure 4. The fact that a second pad may be constructed is borne out by a centrally located control bunker and the presence of two nearly identical launch pads at many of the other SSM launch complexes. A detailed description of all launch area items follows:

Item 1 - Launch pad: The launch pad measures 230 feet on a side and is of concrete construction. It is the largest square pad found at the SSM launch complexes. A concrete loop road, 25 feet wide, provides access to the pad on the southeast side and at the west corner. Drainage ditches are present in the vicinity of the pad, and both the launch pad and service road have been graded above the general level of the land to insure proper drainage. On the pad and in line with the road on the southeast side are six vertical poles 20 feet high in two rows of three each. These poles, which have possible cross members on top, form an aisle 50 feet long and 15 feet wide. They may be part of a missile handling structure, supports for a canvas covering, or some other facility in an early stage



FIGURE 3. LAUNCH AREA "E" AND TWO ADJACENT INACTIVE AREAS.

TOP SECRET

PIC/JR-21/60




FIGURE 4. LAUNCH AREA "E". This area contains the largest square launch pad in the SSM launch complexes.

TOP SECRET

TOP SECRET

25X1

PIC/JR-21/60

of construction. A concrete apron extends off the north end of the pad and serves the vehicle revetment and bunker (Items 3 and 4). Four 70-foot-high light standards are located on the northeast and southwest sides of the pad. Lines constructed between diagonally opposite poles pass through the center of the pad.

Item 2 - Control bunker: The control bunker, located in the center of the launch area, 375 feet from the center of the launch pad, is an earth-mounded structure measuring 125 feet square at the base, 70 feet square at the top, and about 10 to 15 feet high. Possibly five objects are on top of the bunker. Two probable cable trenches lead from near the bunker to the pad. Access is gained through a personnel entrance in the north side of the bunker. If a second pad were to be constructed, this bunker would probably serve both.

Item 3 - Vehicle revetment: This revetment, which abuts the northwest side of the pad, is 50 feet long and 25 feet wide. It may serve as an entrance beneath the pad or as protection for launch support equipment. At least three other launch areas in the SSM facilities have a similarly positioned revetment. The road leading to this revetment, the concrete apron, and the northwestern edge of the launch pad delineate a dark, slightly depressed, circular area, 70 feet in diameter. No particular significance or function can be attached to this area.

Item 4 - Vehicle bunker: This bunker consists of a covered section 40 by 20 feet divided into two bays, served by a ramp measuring 50 by 40 feet. It probably serves as protection for launch support equipment. Again, if a second pad were constructed, this bunker might be used jointly.

Item 5 - Two semiburied tanks: Two tanks, 45 feet in diameter and 40 feet apart, are located along a branch of the T-shaped service road. A valve or pump house is situated between the tanks. No pipeline traces can be observed either entering or leaving these tanks.

Item 6 - Three circular ground scars: These scars, one of which has the appearance of being a buried tank, are about 25 feet in diameter. They are located in the northeastern section of the launch area and positioned

TOP SECRET

25X1

PIC/JR-21/60

so as to form a triangle with two sides measuring about 220 feet and one side 290 feet. An unidentified object is near the center of each scar. A linear scar connects two of these circular scars.

Items 7 through 10 - Buildings: These structures are located in a north-south line near the center of the launch area. The largest is a gable-roofed structure (Item 8) measuring 55 by 35 feet. It is probably intended for use by launch personnel but not for active support of firing operations. No functions can be determined for the other three buildings: item 7, 20 by 20 feet, gable roofed; item 9, 30 by 25 feet, flat roofed; and item 10, 25 by 20 feet, flat roofed.

Items 11 through 14 - Buildings: These structures, located between the two security fences near the entrance to the launch area, are concerned with the security and maintenance of the launch area. The security building (Item 11) measures 75 by 30 feet and probably has accommodations for the patrolling troops. A 65-foot-high stack, detached from the building, is located near the south end. The other three buildings are: item 12, 60 by 30 feet, flat roofed; item 13, 45 by 45 feet, hip roofed; and item 14, 25 by 20 feet, gable roofed. Parking hardstands are associated with two buildings (Items 11 and 12). A building similar to item 13 is noted at Launch Area "A" at the Tyura Tam Missile Launch Complex and is believed to be a booster pump house (See CIA/PIC/JR-4/58, page 14).

25X1 ASSEMBLY AND CHECKOUT AREA

The Assembly and Checkout Area, in mid stage of construction in is road served and located just north of the support area of Launch Complex "A" (Figure 5). Its association with Launch Complex "E" is based on its location along the new road to the launch area and the convenient flow pattern evident at the drive-through building. However, since Launch Complex "A" is undergoing modification and expansion, the possibility that this area may have a functional relationship with Complex "A" cannot be overlooked. In either case this area will receive its utility support from Complex "A".

TOP SECRET

25X1

PIC/JR-21/60




FIGURE 5. ASSEMBLY AND CHECKOUT AREA. The large drive-through building in this area was under construction in [redacted]

25X1

The area, which encompasses about nine acres, is enclosed by a fence measuring 725 by 550 feet. Guard towers and a security building were not present at time of photography. Within the area there is an assembly and checkout building and several miscellaneous structures. Outside the security fence is a group of 55 tent bases present in [redacted] a group of 45 tent bases new since [redacted] and four randomly positioned buildings, the largest of which is gabled roofed and measures 90 by 30 feet. Four vehicles are located near one building while about 10 vehicles are observed at various locations inside the fenced area. A detailed description of items within the fenced area follows.

25X1

Item 1 - Assembly and checkout building: This drive-through building, which measures 200 feet long by 130 feet wide, has a total floor space of 26,000 square feet. It consists of a 70-foot-wide, 200-foot-long-clere-story center section flanked by two 30-foot-wide, 25-foot-high workshops. The workshops are roofed; the center section has only the end supports

TOP SECRET

25X1

PIC/JR-21/60

in position. Two rows of windows are visible on one side of one workshop. The entrance to the clerestory center section will be about 45 feet wide. A parking hardstand is being constructed at both ends of the building. An open ditch, probably for a steam line leads from the southern corner of the building, across the road, and past the steam/heat plant in the support area of Launch Complex "A". A building under construction at a new rail-served assembly and checkout area at Launch Complex "C" is similar in plan view and dimensions.

Items 2 through 4 - Buildings: No particular function other than general support can be ascribed to these three single-story structures, which measure 30 by 20 feet, 40 by 20 feet, and 60 by 15 feet, respectively.

Item 5 - Sump or pit: This is an excavation 30 feet square which has two parallel earth scars leading from it.

CONCLUSIONS


Launch Complex "E" is a road-served ballistic missile launch facility to be used in the research and development of a new missile system. It should be operational by mid-1960. Although one launch pad is present, it is expected that a second pad will eventually be constructed. Since no instrumentation facilities can be associated with the complex, it is assumed either that they are yet to be constructed or that the missile will use existing test range instrumentation. Since both the launch pad and the assembly and checkout building are large when compared with those at the other SSM launch complexes, it is possible that the missile to be fired from Launch Complex "E" is as large as or larger than those fired from the other SSM launch complexes.

PIC/JR-21/60

REFERENCES

25X1

PHOTOGRAPHY




MAPS or CHARTS

- CIA. 11995, The Lower Volga Area East of Stalingrad, Jun 52 (6-52), Scale 1:300,000 (S)
- AMS. Series N501, Sheet NM 38-11 (Stalingrad), 3d ed, Scale 1:250,000 (U)
- AMS. Series N501, Sheet NM 38-12 (Petropavlovskyy), 2d ed, Scale 1:250,000 (U)
- SAC. US Air Target Chart, Series 200, 0235-22 AL, 3d ed, May 60, Scale 1:200,000 (S)

DOCUMENTS

25X1

Air, AFIC. DPIR T60-8, Jan 60 [redacted]



25X1

25X1

25X1

Approved For Release 2003/02/27 : CIA-RDP78T04751A000400010041-6

Approved For Release 2003/02/27 : CIA-RDP78T04751A000400010041-6